


Activity	Duration Weeks	Trade	Resources	Manhours	Hourly Rate	Total
Prepare Site Level site for concrete slab	1	Machine operator	2	10	\$ 120.00	\$ 1,200.00
Concrete Slab Construct formwork	1	Concretor	4	20	\$ 65.00	\$ 1,300.00
Lay reinforcement mesh	1	Concretor	4	20	\$ 65.00	\$ 1,300.00
Pour concrete	1	Concretor	4	20	\$ 75.00	\$ 1,500.00
Wall Frames Construct timber frames	2	Carpenter	3	30	\$ 85.00	\$ 2,550.00
Install windows	1	Carpenter	2	10	\$ 85.00	\$ 850.00
External Walls Lay brick walls	2	Brick layer	4	40	\$ 70.00	\$ 2,800.00
Render brick walls	1	Renderer	2	10	\$ 75.00	\$ 750.00
Construct Roof Construct roof frame	1	Carpenter	2	10	\$ 85.00	\$ 850.00
Install Metal roof sheets and guttering	1	Roofer	2	10	\$ 75.00	\$ 750.00
Internal Walls Lay Cherry timber floor boards	1	Carpenter	2	10	\$ 85.00	\$ 850.00
Install plaster board sheets to all walls	1	Carpenter	4	20	\$ 85.00	\$ 1,700.00
Plaster join and cornices	1	Plasterer	2	10	\$ 75.00	\$ 750.00
Install cherry timber architraves, door	2	Carpenter	2	20	\$ 85.00	\$ 1,700.00
Install doors	2	Carpenter	1	10	\$ 85.00	\$ 850.00
Kitchen and Bathroom Install kitchen cabinetry	1	Joiner	2	10	\$ 75.00	\$ 750.00
Tile splashbacks and install benchtops	1	Tiler	1	5	\$ 70.00	\$ 350.00
Tile Bathroom wall and floors	2	Tiler	1	10	\$ 70.00	\$ 700.00
Install shower, bath and cabinetry	1	Joiner	2	10	\$ 75.00	\$ 750.00
Painting Paint external eaves and fascia	1	Painter	2	10	\$ 65.00	\$ 650.00
Paint external rendered walls	2	Painter	2	20	\$ 65.00	\$ 1,300.00
Paint internal ceilings	1	Painter	2	10	\$ 65.00	\$ 650.00
Painting internal walls	3	Painter	2	30	\$ 65.00	\$ 1,950.00
Clean site and handover Clean home internally and externally	1	Cleaner	2	10	\$ 50.00	\$ 500.00
TOTAL						\$ 27,300.00



DRAWING: Labour Resources

SCALE:

DATE: 2/11/2022

STUDENT NAME: Joshua Micallef

PROJECT: Dwelling

PAGE NO. B5

CLASS: CODE2270

STUDENT NO. z5361047



UNSW
AUSTRALIA